

RENCANA ANGGARAN BIAYA (RAB)

PROYEK

: PT. MERSI BIOVAC PROINDO

LINGKUP PEKERJAAN

: CIVIL WORKS DUDUKAN WATER TANK FRP 12,50 x 17,0 m, Kap. 363 m³

LOKASI

: SUKABUMI, JAWA BARAT

PENAWARAN HARGA NO.

:

A. Pekerjaan Struktur & Pedestal					
No	Material	Qty Total	Satuan	Harga Satuan	Harga Total
1	Pasir Pasang	37,34	m³	Rp 380.000	Rp 14.189.200
2	Batu Kali	120,12	m³	Rp 250.000	Rp 30.030.000
3	PC Semen	83	Zak	Rp 50.000	Rp 4.150.000
4	Pasir Pasang	11	m³	Rp 380.000	Rp 4.180.000
5	Wire Mesh M10 - 200 (2,1 x 5,4 m)	38	Lembar	Rp 1.013.000	Rp 38.494.000
6	Besi Beton Ulir 16 mm (12 m)	70	Batang	Rp 160.000	Rp 11.200.000
7	Besi Beton Ulir 10 mm (12 m)	85	Batang	Rp 80.000	Rp 6.800.000
8	Beton Ready Mix K-300, Slump 12±2	85	m³	Rp 950.000	Rp 80.750.000
9	Kawat Bendrat	20	Kg	Rp 25.000	Rp 500.000
Sub Total (A)					Rp 190.293.200
B. Pekerjaan Bekisting & Bouwplank					
No	Material	Qty Total	Satuan	Harga Satuan	Harga Total
1	Papan kayu 2 cm x 20 cm x 4 m	16	Lembar	Rp 30.000	Rp 480.000
2	Triplek 12mm uk. 1220 x 2440	14	Lembar	Rp 110.000	Rp 1.540.000
3	Kayu Kaso 5/7 @4 meter	350	Batang	Rp 8.000	Rp 2.800.000
4	Paku 5 cm	10	Kg	Rp 20.000	Rp 200.000
5	Paku 7 cm	12	Kg	Rp 21.500	Rp 258.000
Sub Total (B)					Rp 5.278.000
C. Alat Kerja					
No	Material	Qty Total	Satuan	Harga Satuan	Harga Total
1	Pompa Cor Long Boom	1	LOT	Rp 7.500.000	Rp 7.500.000
2	Ember Cor Tebal	10	Pcs	Rp 8.000	Rp 80.000
3	Mata Gerinda Cutting 14"	5	Pcs	Rp 55.000	Rp 275.000
Sub Total (C)					Rp 7.855.000
Estimasi Total (A+B+C)					Rp 203.426.200

*Excluded Jasa Pekerjaan


16/7/26