


RENCANA ANGGARAN BIAYA (RAB)						
PROYEK				: PT. MERSI BIOVAC PROINDO		
LINGKUP PEKERJAAN				: HAND RAILING SELASAR BANGUNAN UTAMA		
LOKASI				: SUKABUMI, JAWA BARAT		
PENAWARAN HARGA NO.				:		

A. Pekerjaan Fabrikasi Hand Railing						
No	Material	Ukuran	Qty Total	Satuan	Harga Satuan	Harga Total
1	Besi Hollow Top Rail	50 x 50 x 2,3 mm @6m	45,75	Meter		
			8	Batang	Rp 380.000	Rp 2.897.500
2	Besi Hollow Mid Rail	40 x 40 x 2,3 mm @6m	45,75	Meter		
			8	Batang	Rp 350.000	Rp 2.668.750
3	Besi Hollow Tiang	50 x 50 x 2,3 mm @6m	29,7	Meter		
			5	Batang	Rp 380.000	Rp 1.881.000
4	Base Plate	150 x 150 x 5 mm	27	Pcs	Rp 25.000	Rp 675.000
5	Dynabolt	M10	108	Pcs	Rp 1.500	Rp 162.000
6	Tutup Hollow Plastik	50 x 50 mm	54	Pcs	Rp 1.500	Rp 81.000
7	Cat Dasar Zincromate		8	Kg	Rp 30.000	Rp 240.000
8	Cat Finish Hitam		8	Kg	Rp 35.000	Rp 280.000
9	Thinner		10	Liter	Rp 35.000	Rp 350.000
10	Mata Cutting 4"		10	Pcs	Rp 5.000	Rp 50.000
11	Mata Batu Gerinda 4"		5	Pcs	Rp 11.000	Rp 55.000
12	Kawat Las RD-260 2,6 mm		15	Kg	Rp 25.000	Rp 375.000
13	Mata Bor Beton M10		3	Pcs	Rp 20.000	Rp 60.000
14	Kuas Cat		3	Pcs	Rp 5.000	Rp 15.000
15	Penggaris Besi Siku		1	Pcs	Rp 50.000	Rp 50.000
16	Sikat Kawat		2	Pcs	Rp 20.000	Rp 40.000
Estimasi Total						Rp 9.880.250



07/08/2026
BSR

*Pekerjaan dilakukan ok