

RAB – JALAN UTAMA & RABAT

PT MERSI BIOVAC PROINDO

Rev.03/09/2026

No.	Uraian Pekerjaan	Spesifikasi	Volume	Satuan	Harga Satuan (Rp)	Jumlah (Rp)
1. JALAN UTAMA						
1	Beton K-300	tebal 20cm	193	m³	955.000	184.582.400
2	Beton K-300	tebal 15cm	84	m³	955.000	80.477.850
3	Batu Kapur	Tebal 15cm	269,9	m³	200.000	53.971.200
4	Tie bars	D16 BJTS 30	21	btg	220.000	4.620.000
5	Dowel	D16 BJTP 30	11	btg	260.000	2.860.000
6	Dowel	D25 BJTP 30	20	btg	550.000	11.000.000
7	Besi dudukan	Ø 8mm	551	btg	58.000	31.958.000
8	Wiremesh M10	(optional)	18	lmbr	1.150.000	20.700.000
9	Platic sheet	50m2/roll	60,0	roll	100.000	6.000.000
10	Sewa Baby roller	kap. 2 ton	32,0	jam	150.000	4.800.000
11	Joint sealant aspal jalan	Bitumen seal	12,0	pail	500.000	6.000.000
12	Sewa Mesin Cutting Wheels		3,0	Shift	600.000	1.800.000
13	Damdex	@5 liter	5,0	gln	350.000	1.750.000
TOTAL JALAN UTAMA						410.519.450

2. RABAT						
1	Beton K-175	Tebal 10cm	34,7	m³	820.000	28.454.000
2	Batu Kapur	Tebal 5cm	18,8	m³	200.000	3.760.000
3	Tiebars	D16 BJTS 30	9,0	btg	130.000	1.170.000
4	Besi dudukan	D10	41,0	btg	80.000	3.280.000
5	Platic sheet		5,0	roll	100.000	500.000
TOTAL JALAN RABAT						37.164.000

3. KANSTIN						
1	Kanstin	40x25x15 cm	1.500,0	pcs	35.000	52.500.000
2	Pondasi Batu kali	20x15cm	22,0	m³	200.000	4.400.000
3	Semen		161,0	Zak	50.000	8.050.000
4	Pasir		23,0	m³	380.000	8.740.000
TOTAL KANSTIN						56.900.000
TOTAL KESELURUHAN (JALAN UTAMA + RABAT)						504.583.450

Dibuat Oleh,
SPV Civil & Project

Diperiksa Oleh,
Engineering Manager

Diketahui Oleh,
Project Advisor

Site Head

Catatan : Harga material belum termasuk upah .
(upah harian / borongan)